

Public Works Department



March 1, 2016

TO: All Bidders

RE: "MAJOR STREET REHABILITATION - CITYWIDE (FY 13/14-15/16); PROJECT NO.

428-68548"

ADDENDUM NO. 3

The attached Addendum (2 Pages) revises the Contract Documents and Specifications for:

"MAJOR STREET REHABILITATION - CITYWIDE (FY 13/14-15/16); PROJECT NO. 428-68548"

Please incorporate the revision in your bid and acknowledge receipt of the Addendum on page C-12 of the Proposal. Failure to acknowledge receipt of the Addendum may result in rejection of your bid.

Sincerely,

Matt Pilarz, P.E. Senior Civil Engineer

By:

Natalie Ávila Project Manager

Attachment cc: File

ADDENDUM NO. 3

CITY OF POMONA PUBLIC WORKS DEPARTMENT

"MAJOR STREET REHABILITATION - CITYWIDE (FY 13/14-15/16); PROJECT NO. 428-68548"

February 29, 2016

The following changes shall be made part of the Contract Document and Specifications for:

MAJOR STREET REHABILITATION - CITYWIDE (FY 13/14-15/16); PROJECT NO. 428-68548

and the Bidder shall acknowledge receipt thereof on page C-12 of the Proposal.

CLARIFICATIONS:

Contractor shall obtain Appendix G Disc (Plan 6 of 6 as noted on City's website) from City.

CONTRACT DOCUMENTS AND SPECIFICATIONS

On page C-7 of the Proposal, the bid item no. A-100 is modified to read:

A-100 <u>Two</u> 18" Perforated Smooth Interior Lined Pipes wrapped in Stone Washed Gravel and Non-Woven Geotextile Fabric per Detail on Plan

On page T-59 of the Technical Provisions, the following sentence under LANDSCAPE is added to read:

Contractor shall anticipate a minimum of three (3) utility lines, service laterals, and conduits in each excavation for tree plantings and shall hand dig and protect in place said existing utility lines and conduits and shall split root balls as-needed to fit tree plantings to exiting conditions and include all cost in tree pay items.

On page T-61 of the Technical Provisions, the first sentence under PERFORATED PIPE is amended to read:

This Bid Item shall include all labor, equipment and materials necessary for the infiltration drainage trench including the installation of <u>two</u> 18" perforated smooth interior lined subdrains wrapped in gravel and filter fabric as shown on plans.

On Construction Plans - Garey Ave Infiltration Drainage, the following was revised:

Sheet 6 of 6.

Clarification:

- 1. Bottom invert elevation shown on plans shall be striken from the design. Bottom elevation of the structure is therefore further understood to be about 2' higher with the deletion of the bottom 18" pipe.
- 2. Contractor shall anticipate crossing various utility lines (water, sewer, electric, gas fiber optic, etc) and associated service lines with at least one each existing utility line above and below the proposed infiltration subdrain lines within each ten (10) feet of proposed pipe line and incorporate all costs to protect in place existing utilities and perform the work at the unit prices bid.

On San Antonio Median Improvement Plan is hereby added:

Sheet 1 of 1

Attachments:

- Remove the existing Pages C-1 through C-11 and shall also be Replaced with attached.
- Remove the existing Page T-59 through T-61 and shall also be Replaced with attached.
- Remove the existing Garey Ave Infiltration Drainage Sheet 6 and shall also be Replaced with attached Delta 1 Plan.
- Add attached Sheet 1 of 1 of San Antonio Median Improvement Plan.

*****END ADDENDUM NO. 3*****