



THE CITY OF
POMONA
WATER RESOURCES DEPARTMENT

August 7, 2017

TO: All Bidders

RE: ADDENDUM NO. 2 FOR First Street Improvements - Corporate Yard Facility, Project No. 575-93135

Bid Opening: 11:00 am on August 16, 2017 (Wednesday)

The attached Addendum (4 pages) revises the Contract Documents:

First Street Improvements - Corporate Yard Facility, Project No. 575-93135

Please incorporate the revision in your bid document and return the acknowledgment of the Addendum 3 of the Proposal. Failure to acknowledge receipt of this Addendum may result in rejection of your bid.

Sincerely,

Timotheus Hampton, PE
Senior Water Resources Engineer

Attachments

cc: File

ADDENDUM NO. 3

**CITY OF POMONA
PUBLIC WORKS DEPARTMENT**

First Street Improvements– Corporate Yard Facility, Project No. 575-93135

The following change shall be made part of the Contract Document for:

First Street Improvements– Corporate Yard Facility, Project No. 575-93135

The Bidder shall acknowledge the Confirmation of Receipt of Addendum No. 3 for the subject project.

CONTRACTOR QUESTIONS:

1. In the detail for the motorized swing gate at the entrance of the project there is a safety loop shown on the street side of the gate but no asphalt or concrete is shown extending out in that area on the plan. Please clarify how far out you want the asphalt to go in order to make this loop work.
 - A. Extend the asphalt 10-ft outside. Loop shall be installed in 4-ft distance from the gate

CONTRACT DOCUMENTS (Plans and Specifications):

1. Pages C-2 to C-4 to of the Contract Documents is revised as attached.
2. SECTION 01010 SUMMARY OF WORK is revised by adding a new subsection 1.3.11 SWPPP AND BMP IMPLEMENTATION (LUMP SUM) to read as follows:

Payment for SWPPP/NPDES/BMP's shall be made at the Contract unit bid price per lump sum (LS), as shown in the Bid Schedule, and shall include preparing a SWPPP, Erosion Control/Sedimentation Plans, implementing SWPPP, including Best Management Practices (BMP's), monitoring and reporting (if required), and modifying SWPPP as needed during the construction. Contractor shall submit SWPPP prepared by a qualified preparer along with Erosion/Sedimentation Control Plans to City for review and approval, prior to the start of the construction, Once SWPPP is approved and prior to the start of the construction, Contractor or its SWPPP preparer shall be responsible to file the Permit Registration Documents through the State Water Board's SMARTS database system.

This item shall be considered full compensation for doing all work as specified herein. Progress payments for this item shall be paid for in accordance with the completion percentage of the project.

*******END ADDENDUM NO. 3 *******

**PROPOSAL
FOR
FIRST STREET SITE IMPROVEMENTS**

TO CITY OF POMONA

The undersigned hereby proposes and agrees to perform all the work and improvements therein described, and to construct the City of Pomona Temporary Water Resources Department Corporate Yard Facility improvements as indicated. The major items of work are as follows, but are not limited excavation, site grading, tree removals, gate installations, material bin construction, electrical improvements site lighting installation, detention basin construction, and AC paving within limits shown on contract documents.

Each line item bid shall contain all costs and expenses for the work described in the identified numbered bid item.

BASE BID SCHEDULE					
ITEM #	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL COST
1	MOBILIZATION, DEMOBILIZATION, AND PERMITS	1	LS	\$	\$
2	AC PAVEMENT REMOVAL	1	LS	\$	\$
3	REMOVAL OF EXISTING FENCE AND GATES	1	LS	\$	\$
4	REMOVAL OF TREES	1	LS	\$	\$
5	SITE GRADING	1	LS	\$	\$
6	CONCRETE GUTTER CONSTRUCTION	442	LF	\$	\$
7	CONSTRUCT REINFORCED CONCRETE MATERIAL BIN	1	LS	\$	\$
8	CONSTRUCT REINFORCED CONCRETE BUILDING SLAB	1	LS	\$	\$
9	PROVIDE AND INSTALL ELECTRIC LIGHTINGS	11	EA	\$	\$

10	PROVIDE AND INSTALL ELECTRICAL SERVICE, AND CONDUITS	1	LS	\$	\$
11	CONSTRUCT REDWOOD HEADERS	926	LF		
12	CONSTRUCT AC PAVEMENT	64,374	SF	\$	\$
13	CONSTRUCT MOTOR OPERATED GATE	1	EA		
14	CONSTRUCT WROUGHT IRON FENCE W/ CURVED PRESSED PICKETS	659	LF	\$	\$
15	SWPPP AND BMP IMPLEMENTATION	1	LS	\$	\$
TOTAL BASE BID AMOUNT:					\$

TOTAL BASE BID AMOUNT IN WORDS:

ADDITIVE BID SCHEDULE A

ITEM #	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL COST
A-1	CONSTRUCT PRE-FABRICATED MATERIAL BIN CANOPY	1	LS	\$	\$
A-2	CONSTRUCT DETENTION BASIN	1	LS	\$	\$
TOTAL ADDITIVE BID SCHEDULE A AMOUNT:					\$

TOTAL ADDITIVE BID SCHEDULE A AMOUNT IN WORDS:

ADDITIVE BID SCHEDULE B

ITEM #	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL COST
B-1	CONSTRUCT PREFABRICATED METAL BUILDING SYSTEM	1	LS	\$	\$
B-2	CONSTRUCT PREFABRICATED METAL BUILDING SYSTEM ELECTRICAL COMPONENTS	1	LS	\$	\$
TOTAL ADDITIVE BID SCHEDULE B AMOUNT:					\$

TOTAL ADDITIVE BID SCHEDULE B AMOUNT IN WORDS: